

NOTICE INVITING TENDER

Sub. : Up gradation of Earthing System by Maintenance Free Chemical Earthing at SCOPE Minar Laxmi Nagar, Delhi-110092.

1. Sealed item rate tenders are invited by Dy. General Manager, SCOPE Minar on **behalf of Constituents of SCOPE Minar, Laxmi Nagar Delhi- 110092** for the subject work as per the details given below.
 - 1.1 Name of the work : **Up gradation of Earthing System by Maintenance Free Chemical Earthing at SCOPE Minar, Laxmi Nagar, Delhi-110092.**
 - 1.2 Estimated Cost : **Rs.3,40,220.00/-.**
 - 1.3 Earnest Money : **Rs.7000.00/-.**
 - 1.4 Time for completion : **2 months from the date of issuance of WO.**
 - 1.5 Cost of Tender : **Rs. 500.00**
 - 1.6 Last date of submission of Tenders : **03.01.2017 upto 3.00 P.M.**
 - 1.7 Place of submission of Sealed Tenders : **Office of Dy.General Manager , SCOPE Minar, Core-2, UL Floor, SCOPE Minar, Laxmi Nagar. Delhi – 110092**
 - 1.8 Date & Time opening of Tenders : **03.01.2017 at 3.30 P.M.**
 - 1.9 Place of opening of Tenders : **As mentioned above.**
2. Tender documents consisting of Technical specifications, schedule of quantities, contract conditions, can be had from the office of Dy. General Manager, SCOPE Minar, Core – 2, UL Floor, SCOPE Minar, Laxmi Nagar, Delhi – 110092 on payment of **Rs.500/-** in Draft in favour of **“MMO SCOPE Minar”** (Non-refundable) on any working day from 23.12.2016 to **02.01.2017** during working hours from 10.00 A.M. to 2.30 P.M.**only.**
3. Tender document shall be issued only to specialized Contractors / Manufactures working with CPWD/PWD/MES/Railway/PSUs/Autonomous Bodies who fulfill following pre-qualification criteria:

3.1 Proof of registration with, Service Tax, VAT clearance certificate & PAN No.

3.2 Experience of having successfully completed similar works during the last 5 years ending last day of the month previous to the one in which applications are invited:

Three similar completed works, each costing not less than the amount equal to 40% of estimated cost put to tender.

OR

Two similar completed works, each costing not less than the amount equal to 60% of the estimated cost put to tender.

OR

One similar completed work of aggregate cost not less than the amount equal to 80% of the estimated cost.

4 **The tender shall be submitted in the following manner, in two separate sealed envelopes, duly superscribed the name of work alongwith following details:-**

Envelope-I “EMD”

Envelope-II “Technical and priced Commercial Bid”

Envelope – I shall contain ‘EMD’. Envelope-II shall contain tender containing Technical & priced Commercial Bid duly signed and stamped on all pages. It is to be noted that the sealed envelope containing tender documents (Envelope-II) shall contain only the prices without any conditions whatsoever.

5 Tenderers are advised to submit their offers strictly based on the design parameters, Specific requirements, terms & conditions and specifications given in the tender document.

6 Earnest Money mentioned above should be paid by crossed Demand Draft / Pay order from any Nationalized / Scheduled Bank in favour of **“MMO SCOPE Minar”**. Tenders without Earnest Money Deposit will be summarily rejected and the representative of such tenderers will not be allowed to attend tender opening.

7 The Bids shall be opened on the due date in the presence of tenderers or their authorized representatives who wish to remain present.

8 SCOPE reserves the right to reject any or all tenders without assigning any reasons.

Dy. General Manager

SCOPE OF WORK

There are 40 nos. of conventional type earth pits constructed on the outer periphery of the building premises. These earth pits are to be reconstructed by new maintenance free chemical earthing. The scope of work commences from:

- Construction of required no. of maintenance free chemical Earth Pits around the outside periphery of the Building premises.
- All the Earth Pits shall be interconnected by GI Earth strips of suitable sizes forming Earth Ring / Grid.
- Contractor has to check the connectivity of the existing earth ring.
- If any portion in the existing earth ring found broken, same shall be reconnected with GI strip of suitable size.
- After ensuring the healthiness of the Earth Rings, same shall be connected with the new constructed earth pits.
- The Earth Strip crossing the Ramp / Road shall be saddled on the wall or on beam over the passage as per site condition.
- The agency shall be responsible for testing the earth resistance values of each earth pits and the average value of earth grid.

Note : This work is to be executed on turnkey basis and any item not specifically mentioned in the scope of work or Bill of Quantity (BOQ) is deemed to be included in the overall value of contract and shall also deemed to include for all the activities, labour, materials, machineries, tools and plants required for the satisfactory execution of work for all leads and lifts. Nothing extra shall be payable. The contractor must ascertain himself with the site conditions, nature of work, disposal route etc. before quoting for the work.